

Section 09545 - Specialty Metal Ceilings

Part 1 – General

1.01 Scope

- A. Furnish and install the Cell Metal Tile ceiling system as manufactured by Steel Ceilings Inc., Johnstown, Ohio.

1.02 Related Sections

- A. Section 09510 Acoustical Ceilings
- B. Section 09250 Plaster and Gypsum Board
- C. Section 15550 Heating, Ventilating and Air-conditioning
- D. Section 16500 Lighting

1.03 References

- A. American Society for Testing and Materials (ASTM)
 - 1. C635 - Standard specification for the manufacture, performance and testing of metal suspension systems for acoustical tile and lay - in panel ceilings.
 - 2. C636 - Standard practice for installation of metal ceiling suspension systems for acoustical tile and lay-in panels.
 - 3. E84 - Test method for surface burning characteristics of building materials.
- B. CISCA – Ceilings and Interior Systems Construction Association

1.04 Submittals

- A. Provide product data sheets listing dimensions, style, edge detail, perforation pattern and finish.
- B. Alternates require prior approval no later than 21 days prior to bid date. In addition to the requirements in A above, submittals for approved alternates must include samples of actual products to be substituted together with test certificates supporting performance claims, a mock up and a written warranty.

1.05 Project Conditions

- A. Environmental Requirements
 - 1. Area to receive ceiling systems shall be protected from the weather.
 - 2. Wet trades work shall be complete and dry prior to installation of ceiling system.
 - 3. Installation shall not proceed until the temperature and humidity conditions closely approximate finish condition.

1.06 Attic Stock

- A. Provide 2% (3% etc) of the ceiling system area materials to be used as attic stock.

1.07 Performance

- A. Materials and installation must comply with Local Building Code and Regulations
- B. Materials should be stored and handled in accordance with CISCA's *Acoustical Ceilings – Use and Practice*
- C. Materials to comply to CISCA's *Metal Ceilings Technical Guidelines*
- D. There are no special seismic requirements

Part 2 - Products

2.01 Manufacturer

- A. Cell Metal Pans shall be as manufactured by Steel Ceilings Inc., Johnstown, Ohio.
www.steelceilings.com

2.02 Materials

- A. Suspension System
 - 1. T-Bar suspension system shall be formed from galvanized steel(aluminum) and shall be intermediate duty with face dimension of 9/16". Main runners shall be spaced not to exceed 48" on center by direct suspension from the existing structure with not less than 12 gauge pre-straightened hanger wires, wrapped tightly 3 full turns, spaced 48 inches on center.
 - 2. Wall molding shall be formed from galvanized steel (aluminum) in L shape to receive metal pans.
- B. Cell Metal Panels
 - 1. Metal pans shall be formed from .018" aluminum to form blades with a 9/16" face and vertical sides of 1 1/2"(2" or 3") to form equally spaced cells of 3" x 3"(4" x 4", 6" x 6", 8" x 8").
 - 2. Panels shall be square 24" x 24".
 - 3. Panels shall be post painted to seal all edges with polyester powder global white (color) gloss level 12% to 15%.

Part 3 – Execution

3.01 Examination

- A. Installer must inspect the area that is to receive the metal ceiling system for conditions that may affect the installation and notify, in writing, any conditions that must be rectified before commencing.
- B. All work above the ceiling shall be completed before proceeding with this installation.
- C. All wet work shall be completed and thoroughly dry before proceeding with this installation.

3.02 Installation

- A. Metal Ceiling components shall be delivered in unopened cartons and shall be clearly marked with manufacturer's name.
- B. Material shall be stored in dry and protected areas.
- C. Install the ceiling system in accordance with the manufacturer's recommendations and the approved shop drawings.
- D. Cut panels shall, where possible, not be less than one half of full size.
- E. Panels shall be free from defects and damaged panels shall be removed and replaced.